

ITEM NUMBER: 18.2

CONFIDENTIAL REPORT

FINAL DESIGNS – CHAPEL STREET PLAZA & HINDMARSH LANE

Pursuant to Section 83(5) of the Local Government Act 1999 the Report attached to this agenda and the accompanying documentation is delivered to the Council Members upon the basis that the Council consider the Report and the documents in confidence under Part 3 of the Act, specifically on the basis that Council will receive, discuss or consider:

b. Information the disclosure of which could reasonably be expected to confer a commercial advantage on a person with whom the council is conducting, or proposing to conduct, business, or to prejudice the commercial position of the council; and would, on balance, be contrary to the public interest.

Recommendation – Exclusion of the Public – Section 90(3)(b) Order

- 1 That pursuant to Section 90(2) of the *Local Government Act 1999* Council hereby orders that the public be excluded from attendance at this meeting with the exception of the Chief Executive Officer and Staff in attendance at the meeting in order to consider Report No: 457/19 Final Designs- Chapel Street Plaza and Hindmarsh Lane in confidence.
- 2. That in accordance with Section 90(3) of the *Local Government Act 1999* Council is satisfied that it is necessary that the public be excluded to consider the information contained in Report No: 457/19 Final Designs Chapel Street Plaza and Hindmarsh Lane on the following grounds:
 - b. pursuant to section 90(3)(b) of the Act, the information to be received, discussed or considered in relation to this Agenda Item is information the disclosure of which could reasonably be expected to confer a commercial advantage on a person with whom the Council is conducting business; would prejudice the commercial position of the council.

In addition, the disclosure of this information would, on balance, be contrary to the public interest. The public interest in public access to the meeting has been balanced against the public interest in the continued non-disclosure of the information. The benefit to the public at large resulting from withholding the information outweighs the benefit to it of disclosure of the information.

3. The Council is satisfied, the principle that the meeting be conducted in a place open to the public, has been outweighed by the need to keep the information or discussion confidential.

Item No:	18.2
Subject:	FINAL DESIGNS – CHAPEL STREET PLAZA & HINDMARSH LANE (Report No: 457/19)
Date:	10 December 2019
Written By:	Strategic Planner
General Manager:	Strategy and Business Services, Ms P Jackson

SUMMARY

This report seeks endorsement of final detail design for Chapel Street Plaza and Hindmarsh Lane. The design process led by Jensen Plus and Tonkin over the past 15 months has reached 100% design stage which provides the full suite of documentation required for construction (includes comprehensive engineering information, technical specifications, tender plans, safety in design review and costings). Council endorsement of the final designs will allow a tender process to be undertaken early in the New Year followed by commencement of construction later in 2020, with dates to be confirmed. This will be the first stage of construction of the Jetty Rd Master Plan.

RECOMMENDATIONS

1. That Council endorse the final detailed designs for Chapel Street Plaza and Hindmarsh Lane and commencement of a construction tender process.

RETAIN IN CONFIDENCE - Section 91(7) Order

2. That having considered Agenda Item 18.1 Report No: 457/19 Final Designs – Chapel Street Plaza & Hindmarsh Lane in confidence under section 90(2) and (3)(b) of the *Local Government Act 1999*, the Council, pursuant to section 91(7) of that Act orders that the report, attachment and minutes be retained in confidence for a period of 24 months and that this order be reviewed every 12 months.

COMMUNITY PLAN

Placemaking: Creating lively and safe places Placemaking: Developing walkable connected neighbourhoods Placemaking: Building character and celebrating history Community: Providing welcoming and accessible facilities Economy: Harnessing emerging technology Economy: Boosting our visitor economy Environment: Building an environmentally resilient city

COUNCIL POLICY

N/A

STATUTORY PROVISIONS

Local Government Act Road Traffic Act 1961 BACKGROUND

- The Jetty Road Glenelg Master Plan endorsed on 13 February 2018 (C130218/1032) identifies seven project stages for implementation over the next decade, with Chapel Street Plaza the first priority project for Stage 1 implementation.
- Council committed full funding to undertake detailed design for Chapel Street Plaza in the 2018/19 financial year.
- On 29 January 2019, Council endorsed (Motion C290119/1367) expansion of the project scope and budget to include additional funding for a combined commitment of \$1.8 million for construction of both Chapel Street Plaza and Hindmarsh Lane (subject to matched grant funding).
- Engagement with properties owners and businesses surrounding Chapel Street and Hindmarsh Lane was undertaken on these design concepts from March 2019.
- The Department of Planning, Transport and Infrastructure (DPTI) announced in June 2019 that Council was successfully awarded the construction grant for a value of \$1.7 million plus \$100,000 from Department of Communities and Social Inclusion (DCSI) from a Changing Places Grant.
- At the meeting on 23 July 2019, Council noted (Motion C230719/1557) the feedback received during engagement with key stakeholders on Chapel Street Plaza and Hindmarsh Lane designs and acknowledged that final designs would be brought back to Council for endorsement.

Additional details regarding the project background and chronology are attached.

Refer Attachment 1

REPORT

The Chapel Plaza and Hindmarsh Lane Designs commenced in August 2018 and continued the past 15 months to undertake investigations, concept design, design development, detailed design and documentation stages. The 100% designs are attached.

Refer Attachment 2

Design Update

Since the 70% design stage, a number of improvements and changes to the designs have been made as a result of design refinement and feedback from councillors and stakeholders. The changes include green infrastructure improvements, trees, new stage/platform design, accessibility improvements, street furniture update, and refined lighting designs including

provision for St Andrews Church up-lighting. Further explanation of changes and refinement of the designs since 70% completion and are found in Attachment 3.

Refer Attachment 3

Stakeholder Engagement and Communications

- Those directly impacted by construction and key stakeholders will continue to be engaged with strategies to minimise disruption as a result of construction.
- A licence agreement for the use of the land owned by St Andrew Church within the plaza is yet to be completed. The church continues to have some concerns regarding the usability of new car park access that will be resolved with further negotiation.
- A communications plan will guide continuing engagement with land owners, businesses and residents from design completion through construction.
- Information will be available to interested parties in numerous formats including regularly updated information on the Your Holdfast webpage. Updated photo renders will be used for communications and are found attached.

Refer Attachments 4, 5, & 6

Construction Considerations

There are several practical considerations to ensure that any disruption caused by construction is minimised. The project team will work with the contractor once appointed and determine appropriate solutions alongside adjoining businesses, residents and land owners. Some of these considerations will include:

- Construction start times, duration and work hours;
- Location of site office and materials storage;
- Traffic management and access to Chapel and Milton Streets during construction;
- Location of trades vehicle parking;
- Maintaining access to shops for customers and deliveries; and
- Provision of temporary toilets when amenities buildings are under construction.

Next Steps

Following completion of detailed designs the next steps are as follows:

- December 2019 Council approval of final designs;
- December 2019 residents, businesses and land owners communication;
- January 2020 commence select tender process;
- Feb/March 2020 construction contractor appointed;
- Ongoing 19/20 engagement with properties adjoining project site; and
- TBC 2020 construction start date and duration.

BUDGET

The Chapel Plaza and Hindmarsh Lane total capital estimate is \$3.6 million (including an 11% contingency) with construction to occur over the 2018-19 and 2019/20 financial years. Funding for this project has been provided by a 50/50 contribution from Council and the State Government's Places for People grant fund for construction in 2020. The budget includes provision for all capital works, public art, and up-lighting for St Andrews Church.

Two additional grants have also been awarded from the Department of Communities and Social Inclusion for a Changing Places toilet and also from the State Heritage Branch to upgrade the front steps of the State Heritage listed St Andrews Church.

A summary of construction budget is provided below:

Budget	\$	
Council Contribution	1,721,442	
Places for People Grant	1,770,458	
Changing Places Grant	100,000	
State Heritage Grant	8,100	
TOTAL	3,600,000	

LIFE CYCLE COSTS

On completion of construction, annual maintenance costs will be managed by existing operation budgets with the aim to ensure that materials are selected that are in accordance with depot staff specification. A program for community activation of the space will be developed for once construction is completed. The lifecycles costs have been included in the Long Term Financial Plan and will be updated in the relevant asset management plan following construction.

Chapel Street Plaza Designs – Project Background and Chronology

- The Jetty Road Glenelg Masterplan endorsed on 13 February 2018 (C130218/1032) identifies seven project stages for implementation over the next decade, with Chapel Street Plaza the first priority project for Stage 1 implementation.
- Council was notified being unsuccessful in receiving a 'design and construct' grant for Chapel Plaza in the pre- state election DPTI Places for People Grant round.
- In May 2018, council committed full funding (\$747,500) to undertake detailed design for Chapel Street Plaza and Moseley Square Integration in the 2018/19 financial year.
- An additional \$833,000 was committed towards construction for Chapel Street Plaza and Moseley Square Integration (part 01), subject to matched funding from the 2019 Places for People Grant Fund.
- An open tender selection process appointed a design consultant consortium led by Jensen Plus on 27 August 2018
- Jensen Plus (together with Tonkin, Infraplan, Studio 9, Groundplay and others) were engaged to undertake the detailed designs for Chapel Street Plaza and further develop the concept plan based on the preliminary concept by Oxigen in the Masterplan.
- Between September 2018 and November 2018 detailed design investigations were undertaken and concepts developed during Council election caretaker period.
- The initial Chapel Street concept in the Masterplan identified the possibility of a toilet amenity building at the rear of the Chapel Street site adjacent the Milton St Intersection. However, further investigation found that an amenities building in Chapel Street is difficult to accommodate due to proximity businesses and the State Heritage listed church, loss of public space, vehicle access requirements and visual screening.
- The existing toilet facilities in Hindmarsh Lane, including three Exeloo toilets and the older amenity building in the Coles car park are at capacity and would benefit from upgrading.
- Identified the opportunity to upgrade these facilities including replacement of the Exeloos and upgrades to use a Changing Places toilet grant to upgrade the brick amenity building adjacent the Coles car park with a Changing Places toilet and parenting facility.
- On 29 January council endorsed (Motion C290119/1367) expansion of the scope of the project to include the upgrade of Hindmarsh Lane to allow for consolidation and improvement of existing toilet amenities and improve pedestrian connectivity between the plazas.
- The expanded scope also included the following inclusions since development of the Masterplan including:
 - Open pergola structure over the centre of the Chapel St
 - Public Art budget provision
 - Increased paving area adjoining Milton Street

Chapel Street Plaza Designs – Project Background and Chronology


- Stage area
- Church car park and access modifications
- Brick toilet building adjacent Coles to include a Changing Places toilet
- Council also endorsed additional funding for a combined commitment of \$1.8 million for the Chapel Street Plaza and Hindmarsh Lane upgrade subject to a successful grant application for \$1.8 million (50% contribution) from the State Government's Places for People Grant Fund.
- Also at the January meeting Council endorsed (Motion C290119/1367) the project team to proceed engagement on the concept plans with stakeholders directly impacted by the changes.
- In February 2019 an application seeking matched funding for construction in DPTI Places for People Grant fund round sought matched funding for construction.
- Engagement with the properties and businesses surrounding Chapel Street and Hindmarsh Lane was undertaken throughout March 2019. As a result of the feedback received, a number of changes were made.
- DPTI announced on Friday 21 June 2019 that Council was successful in gaining the grant for this project.
- On 23 July 2019 noted (Motion C230719/1557) the feedback received during engagement with key stakeholders on Chapel Street Plaza and Hindmarsh Lane concepts.
- Council also noted the Chapel Street Plaza and Hindmarsh Lane 70% detailed design milestone and upcoming project stages including further stakeholder engagement and development of final designs and documentation for Council endorsement.

JETTY ROAD, GLENELG MASTER PLAN IMPLEMENTATION STAGE 1: CHAPEL STREET + HINDMARSH LANE LANDSCAPE & IRRIGATION WORKS

(Project No P4818/JR/L) for

CITY OF HOLDFAST BAY NOVEMBER 2019

FOR TENDER





Planning Landscape Architecture Urban Design Social Planning

DRAWING SCHEDULE

JENSEN PLUS

Drawing No.	Title	
P4818 / JR / L100 - Rev D	COVERSHEET	
P4818 / JR / L101 - Rev D	OVERALL SITE PLAN	
P4818 / JR / L102 - Rev D	CHAPEL STREET DEMOLITION PLAN	
P4818 / JR / L103 - Rev D	HINDMARSH LANE DEMOLITION PLAN	
P4818 / JR / L104 - Rev D	CHAPEL STREET HARDSCAPE PLAN	
P4818 / JR / L105 - Rev D	HINDMARSH LANE HARDSCAPE PLAN	
P4818 / JR / L106 - Rev C	CHAPEL STREET LIGHTING + POWER PLAN	
P4818 / JR / L107 - Rev C	HINDMARSH LANE LIGHTING + POWER PLAN	
P4818 / JR / L108 - Rev D	PLANTING SCHEDULE + NOTES	
P4818 / JR / L109 - Rev D	CHAPEL STREET SOFTSCAPE PLAN	
P4818 / JR / L1010 - Rev D	HINDMARSH LANE SOFTSCAPE PLAN	
P4818 /J R / L200 - Rev C	GENERAL DETAILS	
P4818 /J R / L201 - Rev C	PAVING LAYOUT DETAILS	
P4818 /J R / L202 - Rev C	FURNITURE DETAILS	
P4818 /J R / L203 - Rev C	FENCING DETAILS	
P4818 /J R / L204 - Rev B	LIGHTING DETAILS	
GLENELG IRRIGATION	XX-XX	
XX/XX		
TONKIN CONSULTING ENGINEERS	SHEET 00 - 20	
20180894 / REV B		
STUDIO NINE ARCHITECTS	DD03 - DD05	
0919-009		
GROUNDPLAY	01 - 05	
STREET FURNITURE DESIGN		





NOTES:

SPECIFICATIONS.

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT / SUPERINTENDENT.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES . THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL EXISTING AND PROPOSED SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

CONTRACTOR.

REQUIRED.

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

CONSTRUCTION AS DETAILED.


THIS DRAWING MUST BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND


ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE


EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN







SPECIFICATIONS.

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT / SUPERINTENDENT.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES . THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL EXISTING AND PROPOSED SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.

EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

CONSTRUCTION AS DETAILED.

TREE PROTECTION STANDARD

EARTHWORKS.

TREE PROTECTION ZONE: TO AS 4970 SECTION 3. TREE PROTECTIVE MEASURES: TO AS 4970 SECTION 4. MONITORING AND CERTIFICATION: TO AS 4970 SECTION 5.

WORK NEAR TREES HARMFUL MATERIALS: KEEP THE AREA WITHIN THE DRIPLINE FREE OF SHEDS AND PATHS, CONSTRUCTION MATERIAL AND DEBRIS. DO NOT PLACE BULK MATERIALS AND HARMFUL MATERIALS UNDER OR NEAR TREES. DO NOT PLACE SPOIL FROM EXCAVATIONS AGAINST TREE TRUNKS. PREVENT WIND-BLOWN MATERIALS SUCH AS CEMENT FROM HARMING TREES AND PLANTS.

WORK UNDER TREES: DO NOT REMOVE TOPSOIL FROM, OR ADD TOPSOIL TO, THE AREA WITHIN THE DRIPLINE OF THE TREES UNLESS OTHERWISE DOCUMENTED AND APPROVED. EXCAVATION: IF EXCAVATION IS REQUIRED NEAR TREES TO BE RETAINED, GIVE NOTICE AND OBTAIN INSTRUCTIONS. OPEN UP EXCAVATIONS UNDER TREE CANOPIES FOR AS SHORT A PERIOD AS POSSIBLE. CONSIDER NOMINATING THRUST BORING TO AVOID SERVICES TRENCHES WITHIN THE PRIMARY ROOT ZONE. HAND METHODS: USE HAND METHODS TO LOCATE, EXPOSE

AND CLEANLY REMOVE THE ROOTS ON THE LINE OF EXCAVATION. IF IT IS NECESSARY TO EXCAVATE WITHIN THE DRIP LINE, USE HAND METHODS SUCH THAT ROOT SYSTEMS ARE PRESERVED INTACT AND UNDAMAGED. ROOTS: DO NOT CUT TREE ROOTS EXCEEDING 50 MM

DIAMETER. WHERE IT IS NECESSARY TO CUT TREE ROOTS, USE MEANS SUCH THAT THE CUTTING DOES NOT UNDULY DISTURB THE REMAINING ROOT SYSTEM. IMMEDIATELY AFTER CUTTING, WATER THE TREE AND APPLY A LIQUID ROOTING HORMONE TO STIMULATE THE GROWTH OF NEW ROOTS. E.G. FORMULA 20® OR HORMONE 20®. BACKFILLING: BACKFILL TO EXCAVATIONS AROUND TREE

ROOTS WITH A MIXTURE CONSISTING OF THREE PARTS BY VOLUME OF TOPSOIL AND ONE PART OF WELL ROTTED COMPOST WITH A NEUTRAL PH VALUE, FREE FROM WEED GROWTH AND HARMFUL MATERIALS. PLACE THE BACKFILL LAYERS, EACH OF 300 MM MAXIMUM DEPTH, COMPACTED TO A DRY DENSITY SIMILAR TO THAT OF THE ORIGINAL OR SURROUNDING SOIL. DO NOT BACKFILL AROUND TREE TRUNKS TO A HEIGHT GREATER THAN 200 MM ABOVE THE ORIGINAL GROUND SURFACE. IMMEDIATELY AFTER BACKFILLING, THOROUGHLY WATER THE ROOT ZONE SURROUNDING THE TREE.

COMPACTED GROUND: DO NOT COMPACT THE GROUND OR USE SKID-STEEL VEHICLES UNDER THE TREE DRIPLINE. IF COMPACTION OCCURS, GIVE NOTICE AND OBTAIN INSTRUCTIONS.

COMPACTION PROTECTION: PROTECT AREAS ADJACENT THE TREE DRIPLINE. SUBMIT PROPOSALS FOR AN ELEVATED PLATFORM TO SUIT THE PROPOSED EARTHWORKS WATERING: WATER TREES AS NECESSARY, INCLUDING

WHERE ROOTS ARE EXPOSED AT AMBIENT TEMPERATURE

THIS DRAWING MUST BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND

TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN


CONTRACTOR TO COMPLY WITH AS 4970 - 2009


THE CONTRACTOR IS TO DISPLAY A SIGN IN A PROMINENT POSITION AT EACH ENTRANCE TO THE SITE, WARNING THAT TREES AND PLANTINGS ARE TO BE PROTECTED DURING THE


SIGNAGE IS TO BE INSTALLED AND A PROTECTION MEASURES PROGRAMME SUPPLIED BEFORE COMMENCEMENT OF

CONTRACTOR TO PREPARE A TREE PROTECTION PLAN BASED ON THE DESIGN ISSUES SET OUT IN AS 4970 SECTION 2 BEFORE COMMENCEMENT OF EARTHWORKS. EXTENT: ALL TREES NOT MARKED FOR REMOVAL

DAMAGE: PREVENT DAMAGE TO TREE BARK. DO NOT ATTACH STAYS, GUYS AND THE LIKE TO TREES.







THIS DRAWING MUST BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT / SUPERINTENDENT.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES . THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL EXISTING AND

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE

ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE

EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN

CONTRACTOR TO COMPLY WITH AS 4970 - 2009

THE CONTRACTOR IS TO DISPLAY A SIGN IN A PROMINENT POSITION AT EACH ENTRANCE TO THE SITE, WARNING THAT TREES AND PLANTINGS ARE TO BE PROTECTED DURING THE

SIGNAGE IS TO BE INSTALLED AND A PROTECTION MEASURES PROGRAMME SUPPLIED BEFORE COMMENCEMENT OF

CONTRACTOR TO PREPARE A TREE PROTECTION PLAN BASED ON THE DESIGN ISSUES SET OUT IN AS 4970 SECTION 2 BEFORE COMMENCEMENT OF EARTHWORKS. EXTENT: ALL TREES NOT MARKED FOR REMOVAL

TREE PROTECTION ZONE: TO AS 4970 SECTION 3.

TREE PROTECTIVE MEASURES: TO AS 4970 SECTION 4. MONITORING AND CERTIFICATION: TO AS 4970 SECTION 5.

HARMFUL MATERIALS: KEEP THE AREA WITHIN THE DRIPLINE FREE OF SHEDS AND PATHS, CONSTRUCTION MATERIAL AND DEBRIS. DO NOT PLACE BULK MATERIALS AND HARMFUL MATERIALS UNDER OR NEAR TREES. DO NOT PLACE SPOIL FROM EXCAVATIONS AGAINST TREE TRUNKS. PREVENT WIND-BLOWN MATERIALS SUCH AS CEMENT FROM HARMING

DAMAGE: PREVENT DAMAGE TO TREE BARK. DO NOT ATTACH STAYS, GUYS AND THE LIKE TO TREES.

WORK UNDER TREES: DO NOT REMOVE TOPSOIL FROM, OR ADD TOPSOIL TO, THE AREA WITHIN THE DRIPLINE OF THE TREES UNLESS OTHERWISE DOCUMENTED AND APPROVED. EXCAVATION: IF EXCAVATION IS REQUIRED NEAR TREES TO BE RETAINED, GIVE NOTICE AND OBTAIN INSTRUCTIONS. OPEN UP EXCAVATIONS UNDER TREE CANOPIES FOR AS

CONSIDER NOMINATING THRUST BORING TO AVOID SERVICES TRENCHES WITHIN THE PRIMARY ROOT ZONE. HAND METHODS: USE HAND METHODS TO LOCATE, EXPOSE

AND CLEANLY REMOVE THE ROOTS ON THE LINE OF EXCAVATION. IF IT IS NECESSARY TO EXCAVATE WITHIN THE DRIP LINE, USE HAND METHODS SUCH THAT ROOT SYSTEMS ARE PRESERVED INTACT AND UNDAMAGED.


ROOTS: DO NOT CUT TREE ROOTS EXCEEDING 50 MM DIAMETER. WHERE IT IS NECESSARY TO CUT TREE ROOTS, USE MEANS SUCH THAT THE CUTTING DOES NOT UNDULY DISTURB THE REMAINING ROOT SYSTEM. IMMEDIATELY AFTER CUTTING, WATER THE TREE AND APPLY A LIQUID ROOTING HORMONE TO STIMULATE THE GROWTH OF NEW ROOTS. E.G. FORMULA 20® OR HORMONE 20®.


BACKFILLING: BACKFILL TO EXCAVATIONS AROUND TREE ROOTS WITH A MIXTURE CONSISTING OF THREE PARTS BY VOLUME OF TOPSOIL AND ONE PART OF WELL ROTTED COMPOST WITH A NEUTRAL PH VALUE, FREE FROM WEED GROWTH AND HARMFUL MATERIALS. PLACE THE BACKFILL LAYERS, EACH OF 300 MM MAXIMUM DEPTH, COMPACTED TO A DRY DENSITY SIMILAR TO THAT OF THE ORIGINAL OR SURROUNDING SOIL. DO NOT BACKFILL AROUND TREE TRUNKS TO A HEIGHT GREATER THAN 200 MM ABOVE THE ORIGINAL GROUND SURFACE. IMMEDIATELY AFTER BACKFILLING, THOROUGHLY WATER THE ROOT ZONE


COMPACTED GROUND: DO NOT COMPACT THE GROUND OR USE SKID-STEEL VEHICLES UNDER THE TREE DRIPLINE. IF COMPACTION OCCURS, GIVE NOTICE AND OBTAIN


COMPACTION PROTECTION: PROTECT AREAS ADJACENT THE TREE DRIPLINE. SUBMIT PROPOSALS FOR AN ELEVATED PLATFORM TO SUIT THE PROPOSED EARTHWORKS

WATERING: WATER TREES AS NECESSARY, INCLUDING WHERE ROOTS ARE EXPOSED AT AMBIENT TEMPERATURE









ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT / SUPERINTENDENT.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES . THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL EXISTING AND PROPOSED SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

CONTRACTOR.

EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

REQUIRED.


THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

THIS DRAWING MUST BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND

ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE

TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN





PLA	NT SCHEDULE				
TREES		SIZE	QT	QTY	
Ca	Celtis australis	200L	4		
Gt	Gleditsia tricanthos	200L	10	10	
	•				
SHRUBS SPACE SIZE QT				QTY	
Cg	Craspedia globosa 'BIlly Buttons	500mm	140mm	128	
Ku	Kniphofia uvaria	N/A	200mm	8	
Fn	Finica nodosa	650mm	140mm	34	
PaN	Pennisetum alopecuriodes 'Nafray'	650mm	140mm	119	
PtBI	Parthenocissus tricuspidata 'Boston Ivy'	650mm	140mm	8	
Ss	Senecio serpens	650mm	140mm	61	

N/A 45L 7

650mm 400mm 47

NOTE: PLANT NUMBERS FOR CHAPEL ST + HINDMARSH LANE ONLY (REFER TO L109 & L110)

ZfCP Zamia furfuracea 'Cardboard Palm'

Vv Vitis vinifera

TREE PROTECTION STANDARD

CONTRACTOR TO COMPLY WITH AS 4970 - 2009

GENERAL THE CONTRACTOR IS TO DISPLAY A SIGN IN A PROMINENT POSITION AT EACH ENTRANCE TO THE SITE, WARNING THAT TREES AND PLANTINGS ARE TO BE PROTECTED DURING THE CONTRACT.

SIGNAGE IS TO BE INSTALLED AND A PROTECTION MEASURES PROGRAMME SUPPLIED BEFORE COMMENCEMENT OF EARTHWORKS.

TREES TO BE RETAINED

CONTRACTOR TO PREPARE A TREE PROTECTION PLAN BASED ON THE DESIGN ISSUES SET OUT IN AS 4970 SECTION 2 BEFORE COMMENCEMENT OF EARTHWORKS.

EXTENT: ALL TREES NOT MARKED FOR REMOVAL.

TREE PROTECTION

TREE PROTECTION ZONE: TO AS 4970 SECTION 3. TREE PROTECTIVE MEASURES: TO AS 4970 SECTION 4. MONITORING AND CERTIFICATION: TO AS 4970 SECTION 5.

WORK NEAR TREES

HARMFUL MATERIALS: KEEP THE AREA WITHIN THE DRIPLINE FREE OF SHEDS AND PATHS, CONSTRUCTION MATERIAL AND DEBRIS. DO NOT PLACE BULK MATERIALS AND HARMFUL MATERIALS UNDER OR NEAR TREES. DO NOT PLACE SPOIL FROM EXCAVATIONS AGAINST TREE TRUNKS. PREVENT WIND-BLOWN MATERIALS SUCH AS CEMENT FROM HARMING TREES AND PLANTS.

DAMAGE: PREVENT DAMAGE TO TREE BARK. DO NOT ATTACH STAYS, GUYS AND THE LIKE TO TREES.

WORK UNDER TREES: DO NOT REMOVE TOPSOIL FROM, OR ADD TOPSOIL TO, THE AREA WITHIN THE DRIPLINE OF THE TREES UNLESS OTHERWISE DOCUMENTED AND APPROVED. EXCAVATION: IF EXCAVATION IS REQUIRED NEAR TREES TO BE RETAINED, GIVE NOTICE AND OBTAIN INSTRUCTIONS. OPEN UP EXCAVATIONS UNDER TREE CANOPIES FOR AS SHORT A PERIOD AS POSSIBLE.

CONSIDER NOMINATING THRUST BORING TO AVOID SERVICES TRENCHES WITHIN THE PRIMARY ROOT ZONE.

HAND METHODS: USE HAND METHODS TO LOCATE, EXPOSE AND CLEANLY REMOVE THE ROOTS ON THE LINE OF EXCAVATION. IF IT IS NECESSARY TO EXCAVATE WITHIN THE DRIP LINE, USE HAND METHODS SUCH THAT ROOT SYSTEMS ARE PRESERVED INTACT AND UNDAMAGED.

ROOTS: DO NOT CUT TREE ROOTS EXCEEDING 50 MM DIAMETER. WHERE IT IS NECESSARY TO CUT TREE ROOTS, USE MEANS SUCH THAT THE CUTTING DOES NOT UNDULY DISTURB THE REMAINING ROOT SYSTEM. IMMEDIATELY AFTER CUTTING, WATER THE TREE AND APPLY A LIQUID ROOTING HORMONE TO STIMULATE THE GROWTH OF NEW ROOTS. E.G. FORMULA 20® OR HORMONE 20®.

BACKFILLING: BACKFILL TO EXCAVATIONS AROUND TREE ROOTS WITH A MIXTURE CONSISTING OF THREE PARTS BY VOLUME OF TOPSOIL AND ONE PART OF WELL ROTTED COMPOST WITH A NEUTRAL PH VALUE, FREE FROM WEED GROWTH AND HARMFUL MATERIALS. PLACE THE BACKFILL LAYERS, EACH OF 300 MM MAXIMUM DEPTH, COMPACTED TO A DRY DENSITY SIMILAR TO THAT OF THE ORIGINAL OR SURROUNDING SOIL. DO NOT BACKFILL AROUND TREE TRUNKS TO A HEIGHT GREATER THAN 200 MM ABOVE THE ORIGINAL GROUND SURFACE. IMMEDIATELY AFTER BACKFILLING, THOROUGHLY WATER THE ROOT ZONE SURROUNDING THE TREE.

COMPACTED GROUND: DO NOT COMPACT THE GROUND OR USE SKID-STEEL VEHICLES UNDER THE TREE DRIPLINE. IF COMPACTION OCCURS, GIVE NOTICE AND OBTAIN INSTRUCTIONS.

COMPACTION PROTECTION: PROTECT AREAS ADJACENT THE TREE DRIPLINE. SUBMIT PROPOSALS FOR AN ELEVATED PLATFORM TO SUIT THE PROPOSED EARTHWORKS MACHINERY.

WATERING: WATER TREES AS NECESSARY, INCLUDING WHERE ROOTS ARE EXPOSED AT AMBIENT TEMPERATURE > 35°C.

NOTES:

SPECIFICATIONS.

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT / SUPERINTENDENT.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES . THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL EXISTING AND PROPOSED SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

CONTRACTOR.

EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

REQUIRED.


THIS DRAWING MUST BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND


ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE


TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN







NOTES:

SPECIFICATIONS.

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT / SUPERINTENDENT.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES . THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL EXISTING AND PROPOSED SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

CONTRACTOR.

EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

REQUIRED.

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

TREE PROTECTION STANDARD

<u>GENERAL</u>

CONTRACT. EARTHWORKS.

TREES TO BE RETAINED CONTRACTOR TO PREPARE A TREE PROTECTION PLAN BASED ON THE DESIGN ISSUES SET OUT IN AS 4970 SECTION 2 BEFORE COMMENCEMENT OF EARTHWORKS. EXTENT: ALL TREES NOT MARKED FOR REMOVAL.

TREE PROTECTION

TREE PROTECTIVE MEASURES: TO AS 4970 SECTION 4. MONITORING AND CERTIFICATION: TO AS 4970 SECTION 5.

WORK NEAR TREES HARMFUL MATERIALS: KEEP THE AREA WITHIN THE DRIPLINE FREE OF SHEDS AND PATHS, CONSTRUCTION MATERIAL AND DEBRIS. DO NOT PLACE BULK MATERIALS AND HARMFUL MATERIALS UNDER OR NEAR TREES. DO NOT PLACE SPOIL FROM EXCAVATIONS AGAINST TREE TRUNKS. PREVENT WIND-BLOWN MATERIALS SUCH AS CEMENT FROM HARMING

TREES AND PLANTS. DAMAGE: PREVENT DAMAGE TO TREE BARK. DO NOT ATTACH STAYS, GUYS AND THE LIKE TO TREES. WORK UNDER TREES: DO NOT REMOVE TOPSOIL FROM, OR ADD TOPSOIL TO, THE AREA WITHIN THE DRIPLINE OF THE

TREES UNLESS OTHERWISE DOCUMENTED AND APPROVED. EXCAVATION: IF EXCAVATION IS REQUIRED NEAR TREES TO BE RETAINED, GIVE NOTICE AND OBTAIN INSTRUCTIONS. OPEN UP EXCAVATIONS UNDER TREE CANOPIES FOR AS SHORT A PERIOD AS POSSIBLE.

ARE PRESERVED INTACT AND UNDAMAGED. ROOTS: DO NOT CUT TREE ROOTS EXCEEDING 50 MM DIAMETER. WHERE IT IS NECESSARY TO CUT TREE ROOTS, USE MEANS SUCH THAT THE CUTTING DOES NOT UNDULY DISTURB THE REMAINING ROOT SYSTEM. IMMEDIATELY AFTER CUTTING, WATER THE TREE AND APPLY A LIQUID ROOTING HORMONE TO STIMULATE THE GROWTH OF NEW

ROOTS. E.G. FORMULA 20® OR HORMONE 20®. BACKFILLING: BACKFILL TO EXCAVATIONS AROUND TREE

ROOTS WITH A MIXTURE CONSISTING OF THREE PARTS BY VOLUME OF TOPSOIL AND ONE PART OF WELL ROTTED COMPOST WITH A NEUTRAL PH VALUE, FREE FROM WEED GROWTH AND HARMFUL MATERIALS. PLACE THE BACKFILL LAYERS, EACH OF 300 MM MAXIMUM DEPTH, COMPACTED TO A DRY DENSITY SIMILAR TO THAT OF THE ORIGINAL OR SURROUNDING SOIL. DO NOT BACKFILL AROUND TREE TRUNKS TO A HEIGHT GREATER THAN 200 MM ABOVE THE ORIGINAL GROUND SURFACE. IMMEDIATELY AFTER BACKFILLING, THOROUGHLY WATER THE ROOT ZONE SURROUNDING THE TREE.

COMPACTED GROUND: DO NOT COMPACT THE GROUND OR USE SKID-STEEL VEHICLES UNDER THE TREE DRIPLINE. IF COMPACTION OCCURS, GIVE NOTICE AND OBTAIN

INSTRUCTIONS. COMPACTION PROTECTION: PROTECT AREAS ADJACENT THE TREE DRIPLINE. SUBMIT PROPOSALS FOR AN ELEVATED PLATFORM TO SUIT THE PROPOSED EARTHWORKS MACHINERY.

> 35°C.

THIS DRAWING MUST BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND

ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE

TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN

CONTRACTOR TO COMPLY WITH AS 4970 - 2009

THE CONTRACTOR IS TO DISPLAY A SIGN IN A PROMINENT POSITION AT EACH ENTRANCE TO THE SITE, WARNING THAT TREES AND PLANTINGS ARE TO BE PROTECTED DURING THE


SIGNAGE IS TO BE INSTALLED AND A PROTECTION MEASURES PROGRAMME SUPPLIED BEFORE COMMENCEMENT OF


TREE PROTECTION ZONE: TO AS 4970 SECTION 3.

CONSIDER NOMINATING THRUST BORING TO AVOID SERVICES TRENCHES WITHIN THE PRIMARY ROOT ZONE. HAND METHODS: USE HAND METHODS TO LOCATE, EXPOSE

AND CLEANLY REMOVE THE ROOTS ON THE LINE OF EXCAVATION. IF IT IS NECESSARY TO EXCAVATE WITHIN THE DRIP LINE, USE HAND METHODS SUCH THAT ROOT SYSTEMS

WATERING: WATER TREES AS NECESSARY, INCLUDING WHERE ROOTS ARE EXPOSED AT AMBIENT TEMPERATURE





RIVER PEBBLES TO HELP RETAIN CONTRACTOR THEREFORE SHOULD **PROVIDE EVEN COVERAGE ACROSS** ENTIRE BED AT SUITABLE DEPTH TO ENTIRELY COVER FOREST MULCH

(OVERLAID WITH LOOSE, LIGHT COLOURED 50MM SIZED RIVERBED STONES), ACROSS ENTIRE PLANTER BED + WATERING BASIN,

— 50 x 50 x 6mm GALVANIZED STEEL EQUAL ANGLE EDGING FULLY WELDED ON ALL SIDES TO PIN DOWN INTO SUBGRADE BELOW

250mm SPIRAL SHANK FIXING SPIKE TO SECURE GALVANIZED

ROOTSTOP RSB900 RECYCLED ROOT BARRIER SYSTEM FROM SPECIFICATIONS USING BARRIER JOINTING TAPE RST7230 AT JOINTS

NOTES:

THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND SPECIFICATION.

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.


EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.


TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE REQUIRED.

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.


SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN CONSTRUCTION AS DETAILED.





ALL PAVERS TO BE STRAIGHT EDGED + PAVERS TO PROVIDE A FIRM, SLIP **RESISTANT SURFACE TO AS 4586.** ALL CHANGES IN LEVEL BETWEEN **PAVERS (AND BETWEEN PAVERS AND** LIDS ETC) ARE TO BE NO GREATER THAN




Drawn CO

Checked LM

NOTES:

THIS DRAWING SHALL BE READ IN CONJUNCTION WITH



- GOPHER CHARGING STATION

REFER TO ENGINEER'S DRAWINGS

- GOPHER CHARGING STATION TO BE FIXED AS PER MANUFACTURER'S

- PAVING TO ABUT BASE OF GOPHER CHARGING STATION FOOTING REFER TO PLANS AND SPECIFICATION FOR PAVING TYPE

CONCRETE FOOTING AS PER MANUFACTURER'S SPECIFICATION NOTES:

THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND SPECIFICATION.

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.


EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE REQUIRED.

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN CONSTRUCTION AS DETAILED.



CO 191108

CO 191004

CO 19052 BY DATE

FURNITURE DETAILS

JETTY ROAD, GLENELG MASTER PLAN IMPLEMENTATION

CITY OF HOLDFAST BAY





Jensen PLUS

Level 1, 21 Roper Street, Adelaide, South Australia 5000 Tel 08 8338 5511 ww.jensenplus.com.au The information contained in this document is the copyright of Jensen PLUS. Use or copying of the document in whole or part without the written permission of Jensen PLUS constitutes an infringement of Project No. Category Drawing No.

P4818/JR/L202 Date NOV 2019 Scale 1:10 @ A1 Issue FOR TENDER Drawn CO

Revision $\mathbf{\cap}$ Checked LM





TOTAL POLE HEIGHT	FOUNDATION BOLT	Т	D	L	Е	BARS	LIGATURES
5 metres	M16 x 550 x 233 P,C,D	16mm	500mm	1000mm	450mm	N16	240C/C

NOTES:

THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER JENSEN PLUS AND TONKIN ENGINEERING CONSULTANTS, STUDIO NINE ARCHITECTS AND GROUND PLAY, CONTRACT DRAWINGS AND SPECIFICATION.

ALL SETTING OUT TO BE AGREED ON SITE WITH THE LANDSCAPE ARCHITECT.

ALL EFFORTS HAVE BEEN UNDERTAKEN TO PLACE TREES CLEAR OF SERVICES. THE CONTRACTOR IS TO UTILISE DIAL BEFORE YOU DIG SERVICES AND SHALL REPORT ANY DISCREPANCIES OR CLASHES WITH EXISTING SERVICES.

ALL EXISTING SERVICES ON SITE TO REMAIN UNTOUCHED AND PROTECTED DURING THE COURSE OF THE WORKS.

ANY DAMAGE TO EXISTING ROADS AND PAVEMENTS TO BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.


EXISTING ROADS AND FOOTPATHS TO BE KEPT CLEAR OF OBSTRUCTION AND KEPT CLEAN AT ALL TIMES.

TRAFFIC MANAGEMENT TO THE SATISFACTION OF THE RELEVANT AUTHORITY TO BE IMPLEMENTED WHERE REQUIRED.

THE CONTRACTOR SHALL REPORT ANY CLASHES OR DISCREPANCIES WITH EXISTING SERVICES.

SITE MEASUREMENTS TO BE TAKEN WHERE NECESSARY TO ENSURE ACCURACY OF CONSTRUCTION.

CONTRACTORS TO ADVISE OF ANY DIFFICULTIES IN CONSTRUCTION AS DETAILED.



Chapel Street Plaza and Hindmarsh Lane Upgrade –

Final Design Explanation

The following provides an explanation of changes and refinement of designs since 70% completion and answers to outstanding queries.

Environmental Sustainability Improvements

- Green infrastructure will be installed to capture roof stormwater from adjoining buildings will be redirected into the tree beds within Chapel Plaza.
- Garden beds in both Chapel Plaza and Hindmarsh Lane are increased in size to capture additional surface runoff and reduce the expanse of paving.

Trees

- Council arborist assessed the central Hindmarsh Lane Hackberry tree to be in poor health (woolly aphids) and too large for the space and supports removal. One small Gleditsia will be removed in Chapel Plaza.
- Two new Celtis Australis trees will be planted in Chapel Plaza adjacent Jetty Rd, to compliment the 10 new Gleditsia tricanthos and the 5 retained Gleditsias.

New Stage / Platform Design

• This platform replaces the stage structure seen in previous designs. This design will create a point of interest within the plaza and allow for flexible use including sitting and use as a stage for informal and formal use.

Accessibility improvements

- An additional paver type (Austral Black Granite) has been selected to contrast the Juperana stone paving.
- Will be used at edges of spaces (garden beds, parking bays) change in levels (roadway) and for use along the wayfinding navigational strip connecting Chapel Street and Hindmarsh Lane.

Street Furniture Update

- Ergonomics of the bespoke seats have been improved with additional seat overhanging the base.
- Layout and positioning of seats has been reconfigured to maximise use and flexibility.
- Cost of bespoke chairs comparable to proprietary bench in council style guide (recently installed at Minda Coast Park).
- Drinking fountain selected from style guide includes ground level dog bowl.
- Three ash cans will be installed one in Hindmarsh Lane and two in Chapel Plaza.

Lighting

- Reflect new Jetty Rd lighting masterplan and includes provision for up lighting St Andrews Church.
- Smart Lighting Pole will include CCTV and smart controls for energy efficiency.
- Digital sign orientation for safety.

